This is a published notice on the Find a Tender service: <a href="https://www.find-tender.service.gov.uk/Notice/020787-2022">https://www.find-tender.service.gov.uk/Notice/020787-2022</a>

Tender

# **Boundary Wall and Railing Repairs Thorpe Road Cemetery**

Horden Parish Council

F02: Contract notice

Notice identifier: 2022/S 000-020787

Procurement identifier (OCID): ocds-h6vhtk-03575f

Published 29 July 2022, 11:58am

## **Section I: Contracting authority**

## I.1) Name and addresses

Horden Parish Council

Seventh Street

Peterlee

SR8 4LX

Contact

Gemma Rowe

**Email** 

deputy@horden-pc.gov.uk

Country

**United Kingdom** 

Region code

UKC14 - Durham CC

#### Justification for not providing organisation identifier

Not on any register

#### Internet address(es)

Main address

https://horden.parish.durham.gov.uk/

## I.3) Communication

The procurement documents are available for unrestricted and full direct access, free of charge, at

https://horden.parish.durham.gov.uk/

Additional information can be obtained from the above-mentioned address

Tenders or requests to participate must be submitted to the above-mentioned address

## I.4) Type of the contracting authority

Regional or local authority

## I.5) Main activity

General public services

## **Section II: Object**

## II.1) Scope of the procurement

#### II.1.1) Title

Boundary Wall and Railing Repairs Thorpe Road Cemetery

#### II.1.2) Main CPV code

• 45000000 - Construction work

#### II.1.3) Type of contract

Works

#### II.1.4) Short description

This contract involves partial demolition and re-modelling of part of the main boundary wall fronting Thorpe Road Cemetery, Horden, SR8 4TP.

For a tender pack please contact deputy@horden-pc.gov.uk

#### II.1.5) Estimated total value

Value excluding VAT: £80,000

#### II.1.6) Information about lots

This contract is divided into lots: No

#### II.2) Description

#### II.2.2) Additional CPV code(s)

 44000000 - Construction structures and materials; auxiliary products to construction (except electric apparatus)

#### II.2.3) Place of performance

**NUTS** codes

• UKC - North East (England)

Main site or place of performance

SR8 4TP

#### II.2.4) Description of the procurement

Cut back all vegetation in the areas of the works to allow for full access.

Carefully take down the existing boundary wall brick pillars, remove all existing curved copings and reduce the remaining brickwork to the required, lowered height. Clean the retained top course ready for new copings.

Provide a Stihl saw cut through the full thickness of the retained wall at the junction with the lowered pillar in the positions indicated and insert a 10mm thick Aerofil 1 closed cell polyethylene filler to both wall faces to form a new movement joint; point both sides in approved colour polysuphide mastic sealant.

Carefully take down all the identified existing metal railing panels; dispose of the panels identified as being beyond economic repair.

Supply and install new weathered artificial stone copings throughout the length of the identified wall (15 no. panels to the west of the main entrance; 45 no. panels to the east). Thoroughly bed and point throughout.

All retained fencing panels are to be taken off site for repair, adjustment and re-finishing.

Adapt the retained panels to the new profile and manufacture replacement panels as necessary, all as per the detail drawing.

In a workshop environment, allow for specialist blast cleaning of the whole of the retained fencing panels to SA2.5 and for painting in PPG C4 Coating (High Durability). Allow for initial zinc primer / filling prior to priming using SigmaFast 278 @ 120 um; finish using SigmaDur 550H in colour to the CA's choice.

Replacement fence panels to be primed and finished to match.

Manufacture new coupling posts as detailed and finish as per the railing panels.

Allow for providing a single coupling post as a working sample for final approval prior to the manufacture of the remaining units; transport to site and temporarily erect with adjacent fencing panels for the CA's review and further instructions.

Allow for specialist core drilling of the copings in the position of the new post Fixings.

Return the pre-finished fencing panels and new coupling posts to site and secure in position throughout to the pre-drilled fixing positions with SIKADUR 32 epoxy resin, or equal and approved, completely to manufacturer's recommendations. Provide stainless steel bolted fixings between the posts and fencing panels.

Include a contingency sum, to be expended at the discretion of the CA.

#### II.2.5) Award criteria

Price is not the only award criterion and all criteria are stated only in the procurement documents

#### II.2.6) Estimated value

Value excluding VAT: £80,000

#### II.2.7) Duration of the contract, framework agreement or dynamic purchasing system

Duration in months

3

This contract is subject to renewal

No

#### II.2.10) Information about variants

Variants will be accepted: No

#### II.2.11) Information about options

Options: No

#### II.2.14) Additional information

Sealed tender exercise. Email deputy@horden-pc.gov.uk for a tender pack.

# Section IV. Procedure

## **IV.1) Description**

## IV.1.1) Type of procedure

Restricted procedure

## IV.1.8) Information about the Government Procurement Agreement (GPA)

The procurement is covered by the Government Procurement Agreement: No

## IV.2) Administrative information

#### IV.2.2) Time limit for receipt of tenders or requests to participate

Date

19 August 2022

Local time

12:00pm

#### IV.2.4) Languages in which tenders or requests to participate may be submitted

English

# **Section VI. Complementary information**

# VI.1) Information about recurrence

This is a recurrent procurement: No

## VI.4) Procedures for review

VI.4.1) Review body

Horden Parish Council

Peterlee

Country

United Kingdom