

This is a published notice on the Find a Tender service: <https://www.find-tender.service.gov.uk/Notice/022350-2023>

Planning

Modifications to Henderson Dry Dock at the Port of Immingham

Associated British Ports

F01: Prior information notice

Prior information only

Notice identifier: 2023/S 000-022350

Procurement identifier (OCID): ocds-h6vhtk-03ec1f

Published 1 August 2023, 3:32pm

Section I: Contracting authority

I.1) Name and addresses

Associated British Ports

25 Bedford Street

London

WC2E 9ES

Contact

Group Procurement

Email

procurement@abports.co.uk

Country

United Kingdom

NUTS code

UKE13 - North and North East Lincolnshire

Internet address(es)

Main address

<https://in-tendhost.co.uk/abp/asp/Tenders/Current>

Buyer's address

<https://in-tendhost.co.uk/abp/asp/Tenders/Current>

I.3) Communication

Additional information can be obtained from the above-mentioned address

I.4) Type of the contracting authority

Other type

Utility

I.5) Main activity

Other activity

Port Operator

Section II: Object

II.1) Scope of the procurement

II.1.1) Title

Modifications to Henderson Dry Dock at the Port of Immingham

II.1.2) Main CPV code

- 45240000 - Construction work for water projects

II.1.3) Type of contract

Works

II.1.4) Short description

Procurement of the Principal Contractor for the design and construction of works to modify Henderson Dry Dock, remove RORO (Roll On Roll Off) ramps, partially demolish the sill and undertake remodelling works required to the quay. Please respond to this PIN by email to procurement@abports.co.uk

II.1.6) Information about lots

This contract is divided into lots: Yes

II.2) Description

II.2.1) Title

Modifications to Henderson Dry Dock at the Port of Immingham Including Increasing the Depth

Lot No

1

II.2.2) Additional CPV code(s)

- 45240000 - Construction work for water projects
- 45244000 - Marine construction works
- 45241100 - Quay construction work

- 45241400 - Dock construction work
- 45213342 - Ro-ro terminal construction work

II.2.3) Place of performance

NUTS codes

- UKE13 - North and North East Lincolnshire

Main site or place of performance

Port of Immingham

II.2.4) Description of the procurement

The aim of this project is to increase the draft of vessels can be accommodated in Henderson Dry Dock. The design and construction works to be undertaken by the principal contractor will include, but are not limited to the following main elements: Completion of the design. The Contractor will complete the design of the permanent works and undertake the full design and detail of the temporary works including shoring of the HDD (Henderson Dry Dock) walls and cofferdam. Site establishment and preparations. Construction Works - Installing a cofferdam to the front of the Dry Dock; - Pumping out the Dry Dock; - Install temporary works to restrain dry dock walls - Remove and dispose of the remaining sediment to the base of the dry dock; - Break out and remove sill; - Increase the depth of the dry dock by approximately 1m by means of breaking out or planning concrete; - Removal and disposal of the RORO ramps (concrete slab over steel ramp); - Extend broken back dry dock walls (under RORO Ramp) to ground level and make good surrounding paving; - Associated mooring / quay furniture - Removal of cofferdam and other temporary works; - Performance monitoring of the new structure including undertaking surveys during the defects period.

II.2) Description

II.2.1) Title

Modifications to Henderson Dry Dock at the Port of Immingham Excluding Works Associated with Increasing the Depth

Lot No

2

II.2.2) Additional CPV code(s)

- 45240000 - Construction work for water projects

- 45244000 - Marine construction works
- 45241100 - Quay construction work
- 45241400 - Dock construction work
- 45213342 - Ro-ro terminal construction work

II.2.3) Place of performance

NUTS codes

- UKE13 - North and North East Lincolnshire

II.2.4) Description of the procurement

The aim of this project is to modify Henderson Dry Dock to meet business requirements without increasing the depth. The design and construction works to be undertaken by the principal contractor will include, but are not limited to the following main elements: Completion of the design. The Contractor will complete the design of the permanent works and undertake the full design and detail of the temporary works. Site establishment and preparations. Construction Works - Install temporary works to allow breaking out of sill; - Break out and remove sill; - Removal and disposal of the RORO ramps (concrete slab over steel ramp); - Extend broken back Dry dock walls (under RORO Ramp) to ground level and make good surrounding paving; - Removal of temporary works;- Associated mooring / quay furniture

II.3) Estimated date of publication of contract notice

5 September 2023

Section IV. Procedure

IV.1) Description

IV.1.8) Information about the Government Procurement Agreement (GPA)

The procurement is covered by the Government Procurement Agreement: No