

Notes:

All works to be carried out in accordance with the current Building Regulations, British Standards and Codes of Practice and to the satisfaction of the Building Control Body. All dimensions are to be checked on site prior to the commencement of the works. Any discrepancies to be reported prior to the commencement of the relevant works. Please note that paper prints of this drawing may not be an accurate reproduction of the given scale.

Wall Legend:

- General Walls: Unless specified below, all walls to be prepped to receive 2no. coats of white matt paint.
- Kitchenette Splashback: 3mm thick Light Grey Gloss Acrylic Splashback. Side piece to worktop 500mm(h) x 600mm(w). Behind main worktop 500mm(h) x 1800mm(w).
- Full height Wall Cladding: Polyflor - Polyclad Pro PU - Dusted Blue 4096. Cladding to be finished with Polyflor CT capping strip (White 9520) - see skirting details below.
- Kitchenette Splashback: 3mm thick Light Grey Gloss Acrylic Splashback. Side piece to worktop 500mm(h) x 600mm(w). Behind main worktop 500mm(h) x 1800mm(w).
- Kitchenette Splashback: 3mm thick Light Grey Gloss Acrylic Splashback. Side piece to worktop 500mm(h) x 600mm(w). Behind main worktop 500mm(h) x 1800mm(w).

Floor Legend:

- Anthracite Grey sheet carpet flooring. Stainless steel carpet strips at doors/edges.
- Polyflor Expona Flow PUR - Taupe 9843
- Polyflor SaarFloor Noppe Stud Tile - 707 Cool Blue (Rubber Tiles).
- Heckmondike entrance matting in Anthracite Grey
- Polyflor Acoustix Forest fx PUR Oiled Oak 3095
- Polyflor Camaro Rigid Core PUR - Pearl Micro Terrazzo 4153 (300mm perimeter flooring to corridors)
- Polyflor Polysafe Hydro (to Classrooms) Evolve - Indus 4251
- Polyflor Polysafe Apex 55 - Siltstone 4205.
- Epoxy floor paint - light grey

Skirting

- General Rooms:**
Skirting to all rooms (unless specified otherwise, below) to be 120mm high x 18mm deep square edge MDF timber. Painted with 2 x coats of timber grade paint in Anthracite Grey (RAL 7016). Gloss finish.
- Accessible Changing Room 04:**
Skirting to be formed with Polyflor CF38 cover former to perimeter of floor/wall junction with flooring lapped up wall with Polyflor CT capping strip (White 9520).
- Intervention Room:**
Skirting to be formed with Polyflor CF38 cover former to perimeter of floor/wall junction with flooring lapped up wall with Polyflor CS capping strip (Black 9510).
- General:**
Contractor to ensure walls and floors are prepped, cleaned and readied for finishes in accordance with manufacturer's instructions and correct equipment and methods of installation followed/used to ensure any Warranties are validated.

Main Entrance

Proposed GA Floor Layout:

1:50 at A1
0m 0.5m 1m 2.5m 1:50

Rev.	Date:	Description:	Drawn:	Checked:

Client:	Trust Team
Project:	Proposed New Specialist Primary School
Drawing Title:	Floor & Wall Floor Finishes Layout
Project Address:	Land Adj. Stubbin Wood Nursery, Burlington Avenue, Langwith Junction, Nottinghamshire, NG20 9AD.

INCO-24-108-(40)-001	T1		
TENDER ISSUE			
Drawn: LF	Checked: CH	Scale (Size): 1:50 @ A1	Date: April 2025

INCO Architecture

part of
INCO Construction & Development Consultants
Address: 22 Green Lane, Derby, DE1 1RY
T: 01332 315846 E: info@inco-cdc.co.uk W: www.inco-cdc.co.uk

TRUST · COLLABORATION · INTEGRITY · DEDICATION

© 2025. This drawing is copyright of Inco Architects and must not be copied or reproduced without prior written approval of Inco Architecture/The Berry Group. All rights reserved.

Paper/Check Size:
0 10mm 20mm