

Contractor Design Portion - Project Specifics



Client: College Of Policing
Project: Norwich Lounge Refresh
No: CDP-E01

Project Ref: NTBS4286
Date: 29th May 2025
Gleeds M&E Project Design/Scope: Stage 3 - With Design Intent

<u>Ref</u>	<u>Discipline</u>	<u>Design Status</u>	<u>Specifics</u>	<u>Gleeds Expectation</u>	<u>Contractor Design Period</u>	<u>Verification/Approval Process</u>
E01	Electrical - Incoming Electrical Supply	Gleeds have provided a Technical Design Solution	Existing to Be Retained - Calculations required to confirm	Contractor to Verify Design Calculations and Maximum Demand Requirements	3-4 Weeks from Contract Instruction	Contractor Shall Provide Own Verification - Gleeds to Approve
E02	Electrical - Mains Distribution	Gleeds have provided a Technical Design Solution	Existing to Be Retained - Indicative Sized CPD's provided by Gleeds for Tender Purposes Only	Contractor to Verify Design Detail & Calculations	3-4 Weeks from Contract Instruction	Contractor Shall Provide Own Verification - Gleeds to Approve
E03	Electrical - Sub Distribution	Gleeds have provided a Technical Design Solution	Existing to Be Retained - Calculations required to confirm	Contractor to Complete Technical Design - Contractor Shall Provide Cable Calculations	3-4 Weeks from Contract Instruction	Contractor Shall Provide Own Verification - Gleeds to Approve
E04	Electrical - Earthing and Bonding	Gleeds have provided Indicative Design Details		Contractor to Complete Design	3-4 Weeks from Contract Instruction	Contractor Shall Provide Own Verification
E05	Electrical - Containment	Complete Contractor Design from Stage 3 to Stage 4		Contractor to Complete Design	3-4 Weeks from Contract Instruction	Contractor Shall Provide Own Verification
E06	Electrical - Small Power	Gleeds have provided a Technical Design Solution	Indicative Layouts Provided	Contractor to Complete Technical Design - Contractor Shall Provide Cable Calculations	3-4 Weeks from Contract Instruction	Contractor Shall Provide Own Verification - Gleeds to Approve
E07	Electrical - Lighting and Emergency Lighting	Gleeds have provided a Technical Design Solution	Indicative Lighting Design Layouts Provided and Luminaire Details - Contractor to provide details of luminaires and make allowance for sums as detailed on the drawing/specification	Contractor to Complete Technical Design - Contractor Shall Provide Cable Calculations	3-4 Weeks from Contract Instruction	Contractor Shall Provide Own Verification - Gleeds to Approve
E08	Electrical - Fire Alarm System	Gleeds have provided a Technical Design Solution - Contractor Shall Adopt the Design Certificate	Provisional Sum allowed for additional detectors should the client verify - Contractor to Employ Nominated Specialist	Contractor Shall Complete Design via the Nominated Specialist	3-4 Weeks from Contract Instruction	Contractor Shall Provide Own Verification - Gleeds to Comment

Contractor Design Portion - Project Specifics



Client: College Of Policing
Project: Norwich Lounge Refresh
No: CDP-E01

Project Ref: NTBS4286
Date: 29th May 2025
Gleeds M&E Project Design/Scope: Stage 3 - With Design Intent

<u>Ref</u>	<u>Discipline</u>	<u>Design Status</u>	<u>Specifics</u>	<u>Gleeds Expectation</u>	<u>Contractor Design Period</u>	<u>Verification/Approval Process</u>
E09	Electrical - Retained Systems	Gleeds have provided a Technical Design Solution	Existing Electrical Services identified as retained - Contractor to make allownaces for these services as Identified on the drawing/specification	Contractor to Adopt and Verify	During Site Survey/Site Prescence	Contractor Shall Provide Own Verification - Gleeds to Approve