INVITATION TO TENDER REQUEST FOR TENDER FOR THE SUPPLY OF ARBORICULTURAL WORKS WITHIN MIDSOMER NORTON TOWN PARK.

OPENING DATE: 14TH NOVEMBER 2025 CLOSING DATE: 5TH DECEMBER 2025 (MIDDAY)



MIDSOMER NORTON TOWN COUNCIL

REQUEST FOR TENDER FOR THE SUPPLY OF ARBORICULTURAL WORKS WITHIN MIDSOMER NORTON TOWN PARK.

Contents

Introduction	2
2.0 Term of the Contract	2
3.0 Contract Award	3
4.0 Specification	3
5.0 Payment terms	4
6.0 Pricing	5
7.0 Sub-contractors to any quotation	5
8.0 Organisational compliance	5
9.0 Specification Compliance	6
10.0 General compliance	7
11.0 Additional Information	7
12. Tender Submission	7
Appendix A – Tree work schedule	8
Appendix B – Tree work plans	. 13

TENDER

Introduction

- 1.1 Midsomer Norton Town Council have invited you to tender for Arboricultural works at the Town Park, off Rackvernal Road, Midsomer Norton.
- 1.2 Please read this document in full and follow the instructions to submit your tender.
- 1.3 Tenders must be submitted for the whole of the Service. Tenders for part only of the service will be rejected.
- 1.4 Prospective tenderers shall ensure that they are fully familiar with the nature and extent of the obligations to be accepted by them if their quotes are accepted, this includes the need to coordinate works on land owned by third parties whose full agreement is subject to their satisfaction regarding the working methodology employed.
- 1.5 The attached documents are and shall remain the property of the town council and shall be returned with the tender and, if no tenders are submitted, on demand.
- 1.6 All Arboricultural work operations within this document have been through planning controls where necessary and Felling Licence FL-018-1337-2023 is granted.

2.0 Term of the Contract

- 2.1 The contract price is required for the whole of the works as specified in the attached specification.
- 2.2 The timeline for the contract is detailed below:

Tender opening date - 14th November 2025
Tender closing date - 5th December 2025 – 12 noon
Evaluation process is anticipated to end 15th December 2025
Town Council selection of contractor on 5th January 2026
Winning supplier anticipated to be contacted on 6th January 2026.
Works on site completed by 13th March 2026.

3.0 Contract Award


- 3.1 The response to this tender will be evaluated by the town council's arboriculturist, Town Clerk and Deputy Clerk, the council is not bound to accept the lowest or any tender. The overall outcome that demonstrates best value and is conducive to the needs of neighbours will be awarded the contract.
- 3.2 The award of this contract will not prohibit the Town Council from purchasing goods/services and/or associated goods/services from alternative suppliers should the contractor be unable to meet the Town Council's requirements such as:
- Delivery timescales.
- Availability of staff with necessary expertise and experience in supporting the required events (equipment and goods).
- · Value for money.
- 3.3 The Town Council reserves the right to seek comparative quotes from other suppliers for single requirements or for specialist services.
- 3.4 Those suppliers who are unsuccessful will be able to request feedback from the town council.

4.0 Specification

- 4.1 The tree work specification for this tender are in the attached Appendices A & B.
- 4.2 In the majority of cases, tree arisings will be left on the town councils' land, where space doesn't permit this tree arisings will be removed from site completely. Where left on site, brushwood below 15cm dia to be chipped and timber over this size will be retained on the ground (which has some risk of rolling depending on topography/log shape & weight). The contractor must therefore aim to cut and leave timber arrested on the ground to avoid this risk. Round timber (without branching) should be left heavy and immoveable and securely rested against a tree if there is a chance of movement. Where tree fellings are carried out in concentrations (i.e at the cycletrack), the timber should be left in a linear row at the foot of the bank/batch (but must be on the town councils land). Timber should not be stacked but left tightly packed (touching) flat on the ground. Advantage should be made of the branched structure to ensure stubs and branches stabilize the timber if necessary.
- 4.3 The works adjacent the cyclepath will require the temporary closure of the path to the public. This closure will require the creation of a diversion route as below. The contractor will need to include for the closure of the path with barriers either end and set up diversion signage that ensures members of the public follow the route. It is anticipated that the workzone will be secured between 8am and 4pm weekdays, the footpath should be opened at the end of the working day and the work site be left without hazards to allow this.

MSN TC treeworks: location of planned path closure and diversion route





4.4 The works adjacent the sports centre car park will require some temporary suspension of parking bays. Dragonfly Leisure have agreed this but some coordination will be needed to implement this subject to their requirements/customer needs. The project arborist will facilitate this element of the work with you/them.

5.0 Payment terms

- 5.1 The Town Council's method of payment is currently by electronic payment.
- 5.2 The Town Council is committed to paying valid invoices within 30 days. The supplier should include details of discounts available for early payment.

6.0 Pricing

6.1 The contract is a fixed price contract and must include all associated costs inclusive of footpath/traffic management and waste removal where detailed.

7.0 Sub-contractors to any quotation

- 7.1 Where a quotation requires third party involvement. The tenderer is asked to seek, where possible, and possibly use any sub-contractors from the local business community of Midsomer Norton.
- 7.2 The Town Council will always seek to use local suppliers and businesses where possible.

8.0 Organisational compliance

- 8.1 Please supply the name and contact details of a single point of contact within your organisation to act as a responsible point for contract delivery. Response:
- 8.2 Please give a brief summary of your organisation, staff structure, staff competency and relevant qualifications required for the delivery of these works, where possible please include an organisation chart.

 Response:

8.3 Please provide details of your Public Liability and Employers insurance and copy of insurance certificate. Response:

9.0 Specification Compliance

9.1 Please	provide in	writing a	total co	st for the	contract.
Response:					

9.2 Please p	provide information o	n how complaints	will be dealt with	for
(a) public on	n the day	·		
Response:				

And

(b) by the Town Council Response:

9.3 Please provide information of third-party companies you will be using, and give details on how you will manage these third party companies including process for checking suitability; Response:

9.4 Please give details on how you will deliver this project by 13th March 2026 if successful, please give details of your timescales plus a brief project plan. Include details relating to any anticipated issues. Response:

9.5 Please give details on how you will manage Health & Safety as part of delivery for this service. Please provide details of your companies Competent Person for H&S and a RAMS/Site Specific Method Statement detailing how the work tasks will be carried out in a safe manner (ensuring working zones are in place across the site, path closure/diversion installation, site being left in safe condition) for this contract. Response:

10.0 General compliance

- 10.1 Please provide information on two (2) other contracts you have successfully delivered, Response:
- 10.2 Please provide the details of 2 references the Town Council could contact where you have successfully delivered similar contracts, Response:
- 10.3 Termination and Notice period either party can terminate this agreement by giving one (1) months' notice in writing.

11.0 Additional Information

- 11.1 It is the responsibility of the prospective tenderers to obtain for themselves, at their own expense, any additional information necessary for the preparation of their quotes.
- 11.2 The Town Council offer the opportunity to visit any site included in the specification.
- 11.3 The tenderer may seek clarification from the Town Council, by way of asking questions of the Deputy Town Clerk via email deputyclerk@msn-tc.gov
- 11.4 The tender document must be treated as private and confidential. Tenderers should not disclose the fact that they have been invited to quote or release details of the tender document other than on an 'in confidence' basis to those who have a legitimate need to know or whom they need to consult for the purpose of preparing the tender.

12. Tender Submission

The tender and all accompanying documents MUST be addressed, in the ordinary course of post, PRIVATE & CONFIDENTIAL to: Deputy Town Clerk, Midsomer Norton Town Council, Somer Centre, Gullock Tyning, Midsomer Norton, BA3 2UH. To arrive no later than 12 noon on 5th December 2025

Tenders received after noon on that date will NOT be considered. EMAIL SUBMISSIONS WILL NOT BE CONSIDERED

Appendix A – Tree work schedule

Tree no	Species	Ht	Spread	Canopy m2	Age class	Condition (good/mod/poor)	Recommendations	Priority
T1	Pine	10	N-S 0 E-W 0	0	М	Poor - dead	Fell, retain stem on ground ensuring it can not roll	1
T2	Pine	10	N-S 0 E-W 0	0	М	Poor - dead	Fell, retain stem on ground ensuring it can not roll	1
T3	Sycamore	12	N-S 6 E-W 5	25	S/M	Poor, extensive die back, 40% ring barked at base, excessive squirrel dam	Fell, retain stem on ground ensuring it can not roll, chip arisings	1
T4	Ash	15	N-S E-W		S/M	Good, healthy, low sagging limb	Remove sagging limb of parking space, chip arisings	1
T5	Sycamore	15	N-S 8 E-W 8	50	S/M	Poor, necrotic bark area circa 50% of circumference, heavy lean to parking area	Fell, remove wood and chip arisings	1
T6	Elm	8	N-S 2 E-W2	3	Υ	Poor, dead	Fell, retain stem on ground ensuring it can not roll, chip arisings	1
T7	Elm	8	N-S 2 E-W 2	3	Y	Poor, dead	Fell, retain stem on ground ensuring it can not roll, chip arising	1
Т8	Sycamore	10	N-S 1 E-W2	2	Y	Poor, dying	Fell 4 marked stems, chip arisings	1
Т9	Pine	15	N-S E-W		М	Poor, dead	Fell, retain stem on ground ensuring it can not roll	1


T10	Ash	17	N-S 2 E-W 2	4	S/M	Poor, 40% ADB, heavily leaning stem over path	Fell leaning stem, retain stems on ground ensuring it can not roll, chip arisings	1
T11	Ash	4	N-S E-W		Y	Poor, leaning stem over path	Fell leaning stem, chip arisings	1
T12	Ash	18	N-S E-W		S/M	Mod, 3 dead limbs over footpath	Remove 3 dead limbs over path circa 10cm dia, chip arisings	1
T13	Ash	13	N-S 2 E-W 2	3	S/M	Poor, dead	Fell, retain stems on ground, chip arisings	1
T14	Ash	18	N-S 8 E-W 8	45	М	Poor, twin stemmed, Polyporus squamosus at base, ADB3	Fell, retain stems on ground as habitat stack, chip arisings	1
T15	Ash	16	N-S 4 E-W 4	12	S/M	Poor, twin stemmed, leaning stem/dead, ADB3	Fell, retain stems on ground, chip arisings	1
T16	Ash	16	N-S 7 E-W 7	40	S/M	Poor, ADB3, 3 stems	Fell, retain stems on ground, chip arisings	1
T17	Ash	18	N-S 2 E-W 2	3	S/M	Poor, ADB3, heavy lean	Fell, retain stem on ground, chip arisings	1
T18	Ash	18	N-S 4 E-W 7	21	S/M	Poor, twin stem, ADB3	Fell, retain stems on ground, chip arisings	1
T19	Ash	16	N-S 6 E-W 3	6	S/M	Poor, ADB3, drawn, 3 stems	Fell, retain stems on ground, chip arisings	1
T20	Ash	18	N-S 6 E-W 3	6	S/M	Poor, ADB3, drawn, 2 stems	Fell, retain stems on ground, chip arisings	1
T21	Ash	16	N-S 6 E-W 3	6	S/M	Poor, ADB3, drawn, 3 stems	Fell, retain stems on ground, chip arisings	1

T22	Ash	18	N-S 2 E-W 2	3	S/M	Poor, ADB3, drawn	Fell, retain stems on ground, chip arisings	1
T23	Ash	18	N-S 8 E-W 8	50	S/M	Poor, ADB3, drawn, 3 stems	Fell, retain stems on ground, chip arisings	1
T24	Ash	18	N-S 2 E-W 2	3	S/M	Poor, ADB3, drawn	Fell, retain stems on ground, chip arisings	1
T25	Ash	18	N-S 6 E-W 3	12	S/M	Poor, co-dominant stem over path, ADB2	Fell, retain stems on ground, chip arisings	1
T26	Ash	18	N-S 6 E-W 7	25	S/M	Poor, ADB3, 3 stems	Fell, retain stems on ground, chip arisings	1
T27	Ash (adj salix)	18	N-S 7 E-W 4	20	S/M	Poor, leaning, ivy, twin stem – only fell leaning stem	Fell leaning stem, retain on ground, chip arisings	1
T28	Ash	15	N-S 3 E-W 3	6	S/M	Poor, ADB4	Fell, retain on ground, chip arisings	1
T29	Ash	15	N-S 7 E-W 7	35	S/M	Poor, ADB3, 2 stems	Fell, retain on ground, chip arisings	1
T30	Ash	8	N-S 1 E-W 2	2	Y	Poor, dead, ADB3	Fell (5 small stems), retain on ground	1
T31	Ash	13	N-S 3 E-W 2	4	S/M	Poor, ADB4	Fell, remove timber, chip arisings	1
T32	Ash	10	N-S 1 E-W 2	1	S/M	Poor, ADB3	Fell, remove timber, chip arisings	1
T33	Ash	8	N-S 1 E-W 2	1	Y	Poor, ADB4	Fell, remove timber, chip arisings	1
T34	Ash	8	N-S 1 E-W 4	3	Y	Poor, ADB4, stems x 4	Fell, remove timber, chip arisings	1


T35	Alder	12	N-S 5 E-W 5	20	Mat	Mod, heavy lean	Fell, remove timber, chip arisings	1
T36	Alder	12	N-S E-W		Mat	Good, 2 leaning stems over path	Remove 2 stems over path, remove timber, chip arisings	1
T37	Ash	8	N-S 2 E-W 2	3	Y	Poor, ADB3	Fell, remove timber, chip arisings	1
T38	Ash	8	N-S 2 E-W 2	3	Y	Poor, ADB3	Fell, remove timber, chip arisings	1
T39	Ash	11	N-S 2 E-W 3	4	Y	Poor, heavy lean	Fell, remove timber, chip arisings	1
T40	Alder	12	N-S 2 E-W 2	3	S/M	Poor, dead, multi-stemmed - heaved	Fell, remove timber, chip arisings	1
T41	Ash	15	N-S 3 E-W 3	10	S/M	Poor, ADB3	Fell, remove timber, chip arisings	1
T42	Larch	15	N-S 0 E-W 0		Mat	Poor, dead	Fell, retain timber on ground	1
T43	Larch	19	N-S 4 E-W 2	3	S/M	Poor, dead	Fell, retain timber on ground	1
T44	Pine	10	N-S 2 E-W 2	2	S/M	Poor, dead	Fell, retain timber on ground	1
T45	Larch	12	N-S 2 E-W 3	4	S/M	Poor, dead, lean over path	Fell, retain timber on ground	1
T46	Larch (tag3796)	15	N-S 2 E-W 1	1	S/M	Poor, tag 3796, dead	Fell, retain timber on ground	1
T47	Larch	15	N-S 0 E-W 0		S/M	Poor, dead	Fell, retain timber on ground	1

T48	Larch	12	N-S 1 E-W 2	1	S/M	Poor, dead	Fell, retain timber on ground	1
T49	Larch	12	N-S 2 E-W 2	3	S/M	Poor, dead	Fell, retain timber on ground	1
T50	Larch	12	N-S 2 E-W 3	4	S/M	Poor, dead	Fell, retain timber on ground	1
T70	Ash	12	N-S 1 E-W 2	1	S/M	Poor, dead	Fell, retain timber on ground	1


Appendix B – Tree work plans



Overall site



Southern area of site



Northern area of site