

Skegness Town Council
Quotation Request – Tree Works December 2025



THE SPECIFIC WORKS									
Location & Ref	Grid Ref	What3words	Species	TPO* ¹	Description & Measurements	Works & Timescale* ³	Tag Ref	Risk* ²	PRICE QUOTED EX VAT
Vine Walk/Beresford Field T001	TF 56386 62285	///curry.asset.youth	Whitebeam (Aria edulis)	No	1x Parkland Tree Height (m): 8 Crown Radius (m): 6 Life Stage: Semi Mature Life Exp.: 10+ Years	Fell to ground level to remove potential risk. Timescale: By 31 st March 2026 		Moderate	
Vine Walk/Beresford Field 176	TF 56384 62217	///ridge.icons.soak	Lawson cypress x70 (Chamaecyparis lawsoniana)	No	x70 Trees which form a hedge Height (m): 17 Crown Radius (m): 4 Trees: 70 Life Stage: Semi Mature Life Exp.: 20+ Years	Reduce lateral spread to the east to suitable growing points retaining a green canopy. Reduce in height by 7m to leave a finished height 10m. Timescale: By 31 st March 2026. As an alternative option please provide the cost of felling and removing these trees. 		Moderate	£ Alternative option to remove.

Skegness Town Council
Quotation Request – Tree Works December 2025

Location & Ref	Grid Ref	What3words	Species	TPO* ¹	Description & Measurements	Works & Timescale* ³	Tag Ref	Risk* ²	PRICE QUOTED EX VAT
Vine Walk/Beresford Field 177	TF 56309 62249	///really.crowd.the mes	English elm (Ulmus procera)	YES	Coppiced. Height (m): 17 Crown Radius (m): 2 Stems: 4 Life Stage: Dead	Fell to ground level. Timescale: By 27 th October 2026. 	Red dots	Moderate	
Vine Walk/Beresford Field 180	TF 56277 62320	///lawn.tribune.duke	Sycamore (Acer pseudoplatanus)	YES	2x Stems Height (m): 11 Crown Radius (m): 2 Stems: 2 Life Stage: Dead	Fell both stems to ground level. Timescale: By 31 st March 2026. 	Red dots	Moderate	
Vine Walk/Beresford Field 181	TF 56337 62271	///name.intent.foster	Sycamore (Acer pseudoplatanus)	YES	1 xTree. Height (m): 13 Crown Radius (m): 6 Life Stage: Dead	Fell to ground level. Timescale: By 31 st March 2026. 	Red dots	Moderate	

Skegness Town Council
Quotation Request – Tree Works December 2025

Location & Ref	Grid Ref	What3words	Species	TPO* ¹	Description & Measurements	Works & Timescale* ³	Tag Ref	Risk* ²	PRICE QUOTED EX VAT
Coronation Walk G001	TF 56726 62532	///chat.invite.dined	Hazel (Corylus avellana) Norway maple x2 (Acer platanoides) Black pine (Pinus nigra) Field maple x2 (Acer campestre) Sycamore x3 (Acer pseudoplatanus)	YES Sycamore only	Group of 9x Trees. Height (m): 12 Crown Radius (m): 6 Trees: 9 Life Stage: Semi Mature Life Exp.: 30+ Years	Reduce the lateral spread to the southeast by 2m to give clearance to the edge of the properties. Prune to keep flowing lines with no internodal cuts Timescale: by 27 th Oct 2026.		Low	
Coronation Walk T001	TF 56480 62113	//zone.export.speaks	English elm (Ulmus procera)	Yes	1x Tree. Height (m): 16 Crown Radius (m): 2 Life Stage: Dead	Fell to ground level. Timescale: By 31 st March 2026.	Red dots	Moderate	



Skegness Town Council
Quotation Request – Tree Works December 2025

Location & Ref	Grid Ref	What3words	Species	TPO* ¹	Description & Measurements	Works & Timescale* ³	Tag Ref	Risk* ²	PRICE QUOTED EX VAT
King George V Walk 189	TF 56161 64541	///farmer.punt.trader	Norway maple (Acer platanoides)	No	1 x Tree. Height (m): 0 Crown Radius (m): 0 Life Stage: Semi Mature Life Exp.:	Fell and replace with a half standard Field maple Timescale: 27-Jan-2026 (3 Months)		Medium	
King George V Walk T002	TF 56121 64431	///bunk.bells.estate	Sycamore (Acer pseudoplatanus)	No	1x Tree. Height (m): 14 Crown Radius (m): 6 Stems: 16 Life Stage: Dead	Fell to ground level. Timescale: By 27 th October 2026.	Red dots	Moderate	
King George V Walk T003	TF 56272 64845	///loaded.haven.metro	Crack willow (Salix fragilis)	No	1x Tree. Height (m): 13 Crown Radius (m): 6 Life Stage: Semi Mature	Fell to ground level. Timescale: By 27 th October 2026.		Moderate	
King George V Walk T005	TF 56325 65029	///outer.learn.heads	Sycamore (Acer pseudoplatanus)	No	1x Tree. Height (m): 12 Crown Radius (m): 2	Fell to Ground level. Timescale: By 27 th October 2026.	Red dots	Moderate	



Skegness Town Council
Quotation Request – Tree Works December 2025

Location & Ref	Grid Ref	What3words	Species	TPO* ¹	Description & Measurements	Works & Timescale* ³	Tag Ref	Risk* ²	PRICE QUOTED EX VAT
					Life Stage: Dead. Collapsing.				
King George V Walk T006	TF 56183 65133	///pills.pirate.rating	Crack willow (Salix fragilis)	No	Multiple trees, previously pollarded. Height (m): 8 Crown Radius (m): 6 Stems: 6 Life Stage:	Re-pollard all willow here. Timescale: By 27 th October 2026.		Medium	
									
King George V Walk 190	TF 56176 64580	///spends.type.smart	Common ash (Fraxinus excelsior)	No	1x Tree. Height (m): 19 Crown Radius (m): 5 Life Stage: Semi Mature	Fell to ground level. Timescale: By 27 th October 2026.	Red dots	Low	
King George V Walk 191	TF 56225 64734	///glow.rents.sobs	Crack willow (Salix fragilis)	No	2x Willow.	Re-pollard willow here. Timescale: By 27 th October 2026.		Low	

Skegness Town Council
Quotation Request – Tree Works December 2025

Location & Ref	Grid Ref	What3words	Species	TPO* ¹	Description & Measurements	Works & Timescale* ³	Tag Ref	Risk* ²	PRICE QUOTED EX VAT
King George V Walk 193	TF 56098 65309	///common.prove.f or mal	Crack willow (Salix fragilis)	No	Multiple trees, previously pollarded.	 Re-pollard all willow here. Timescale: By 27 th October 2026. 		Moderate	
Tower Gardens T008	TF 56799 63237	///meant.gained.ski lls	Horse chestnut (Aesculus hippocastanum)	No	1x Tree. Leans to the South. Height (m): 23 Crown Radius (m): 7.3 Life Stage: Early Mature Life Exp.: 20+ Years	Reduce the lateral spread to the south by 2m to leave a finished length of 8m measured from the main stem. Reduce in height by 5m to give a finished height of 18m. It is prune to keep flowing lines with no internodal cuts. This work is to reduce leverage on the	71	Moderate	

Skegness Town Council
Quotation Request – Tree Works December 2025

						<p>unions and enable the tree to be retained long term. Timescale: By 27th October 2026. See photo next pg.</p> 			
Location & Ref	Grid Ref	What3words	Species	TPO* ¹	Description & Measurements	Works & Timescale* ³	Tag Ref	Risk* ²	PRICE QUOTED EX VAT
Tower Gardens T013	TF 56758 63185	///swept.rots.lobby	London plane x2 (Platanus x hispanica) Norway maple x2 (Acer platanoides)	No	4x Trees. Height (m): 21 Crown Radius (m): 8 Trees: 3 Life Stage: Early Mature Life Exp.: 20+ Years	Reduce the lateral spread to the south to give 2m of clearance to the buildings. Cut to give 30cm of clearance around the lines removing branches less than 2cm diameter. Timescale: Timescale: By 27 th October 2026.	33, 34 NOM 35, 36	Low	

Skegness Town Council
Quotation Request – Tree Works December 2025

Location & Ref	Grid Ref	What3words	Species	TPO* ¹	Description & Measurements	Works & Timescale* ³	Tag Ref	Risk* ²	PRICE QUOTED EX VAT
Tower Gardens T024	TF 56809 63207	///ballots.toned.frost	Horse chestnut (Aesculus hippocastanum)	No	1x Tree. Height (m): 21.7 Crown Radius (m): 10 Life Stage: Mature Life Exp.: 10+ Years	Reduce in height by 5m to leave a finished height of 16.7m. Reduce the lateral spread to the north by 2.5m to leave a finished length of no less than 7.5m - measured from the main stem. Prune to keep flowing lines with no internodal cuts. Works are to reduce leverage on the union. Timescale: By 27 th October 2026 No photo.	41	Moderate	
Tower Gardens T025	TF 56807 63198	///activism.dined.decreased	Horse chestnut (Aesculus hippocastanum)	No	1x Tree. Height (m): 21.3 Crown Radius (m): 11.8 Life Stage: Mature	Reduce the lateral spread to the southeast by 4.8m to leave a finished length of no less than 7m - measured from the main	194	Moderate	



Skegness Town Council
Quotation Request – Tree Works December 2025

Location & Ref	Grid Ref	What3words	Species	TPO* ¹	Description & Measurements	Works & Timescale* ³	Tag Ref	Risk* ²	PRICE QUOTED EX VAT
					Life Exp.: 10+ Years	stem. Prune to keep flowing lines with no internodal cuts. Works are to reduce leverage on the union. Timescale: By 27th October 2026. 			
West Way 189	TF 56658 64996	///lows.copies.finis h	Mixed Species x36	No	36 x Mixed Species Trees. Height (m): 21 Crown Radius (m): 5 Trees: 36 Life Stage: Semi Mature Life Exp.: 10+ Years.	Lift to give 5m of clearance over the road Cut to give 30cm of clearance around the lines removing branches less than 4cm diameter. Cut to clear the street lights. Fell the x2 small sycamore to ground level Timescale: By 27 th October 2026. 		Low	

Skegness Town Council

Quotation Request – Tree Works December 2025

West Way 193	TF 56650 65063	///hats.pigs.cross	Common ash (Fraxinus excelsior)	No	1 x Tree. Height (m): 21 Crown Radius (m): 5 Life Stage: Mature Life Exp.: 10+ Years.	Fell the leaning Ash (marked). Timescale: By 27 th October 2025. 	188	Low	
TOTAL QUOTED PRICE FOR THE SPECIFIC WORKS (Ex VAT)									
TOTAL QUOTED PRICE FOR THE SPECIFIC WORKS INCLUDING ALTERNATIVE OPTION (176)									

Please submit your quotation by 5pm on Monday 5th January 2026. The intention is to decide on works by 15th January 2026; prices are expected to be held for the order to be placed at this time. Works are to be completed within the timescales set within the works schedule with deadlines of either 31st March 2026 or 27th October 2026.

Notes

Trees covered by Tree Preservation order on Vine & Coronation Walk are Ash, Elder, Elm, Larch and Sycamore.

Where a Tree Preservation Order is present an application has been made to East Lindsey District Council to work on the trees, awaiting outcome.

In all cases the price quoted should include the removal of any arisings allowing for any value of the wood removed.

All work on highways and public pavements must be completed following all relevant regulations and with any necessary permits.

All work must be carried out in a way and at a time to avoid disturbing nesting birds.

Any evidence of bat colonies must be reported to the Council as soon as this becomes apparent.

Tower Gardens paths have vehicular weight restrictions (no more than 3 tonnes). This should be taken into account when quoting for the works.

*Skegness Town Council to replace felled trees inhouse, not part of tender.

Skegness Town Council
Quotation Request – Tree Works December 2025

I/We certify that the amount of the Quotation has not been calculated by agreement or arrangement with any other person, firm or company and that the amount of the Quotation has not been communicated to any person, and will not be communicated to any person until after the closing date for the submission of Quotations.

Signed: Date:

1. Please give brief details of any relevant experience and any similar works undertaken. Please include details of the person who will supervise the works including their qualifications (copies of certificates to be attached)

--

2. Please provide details of qualifications and enclose copies of certificates of all other workers that will work on the contract.

--

3. Please give details and provide copies of risk assessments, working practices and work method statements to ensure compliance with BS3998 and all Health and Safety Requirements

Skegness Town Council
Quotation Request – Tree Works December 2025

4. Please confirm that you accept responsibility for assessing and managing all risks to yourselves and members of the public in the course of carrying out any works on behalf of Skegness Town Council.
YES / NO
6. Please enclose a copy of your Public Liability Insurance certificate.